

1 Evaluation of lean off-site construction literature through the lens of 2 Industry 4.0 and 5.0

3 Ali Hadi ¹; Franco Cheung ²; Solomon, Adjei ³; Anmar Dulaimi ⁴

4 ¹ School of Engineering and the Built Environment, Birmingham City University, Birmingham, UK
5 (corresponding author). ORCID: <https://orcid.org/0000-0002-9411-1283>. Email: ali.hadi@mail.bcu.ac.uk

6 ² School of Engineering and the Built Environment, Birmingham City University, Birmingham, UK. ORCID:
7 <https://orcid.org/0000-0001-6088-6315>. Email: franco.cheung@bcu.ac.uk

8 ³ School of Engineering and the Built Environment, Birmingham City University, Birmingham, UK. ORCID:
9 <https://orcid.org/0000-0001-5712-6171>. Email: solomon.adjei@bcu.ac.uk

10 ⁴ College of Engineering, University of Warith Al-Anbiyaa, Karbala, Iraq; School of Civil Engineering and Built
11 Environment, Liverpool John Moores University, Liverpool, UK. ORCID: <https://orcid.org/0000-0002-6014-866X>. Email: A.F.Dulaimi@ljmu.ac.uk
12

13 Abstract

14 Lean manufacturing principles are being increasingly employed in off-site construction (OSC), with the
15 primary objective to reduce waste and improve production efficiency. This is performed using several
16 tools and technologies largely influenced by the concept of Industry 4.0 (I4.0) which sets fundamental
17 design principles for technological development. However, the recent introduction of the concept of
18 Industry 5.0 (I5.0) extends I4.0 focus towards wider economic, social, and environmental implications.
19 This study aims to evaluate extant literature employing lean tools and concepts in OSC towards the
20 realisation of I4.0 and I5.0 design principles, identifying key research themes and gaps and suggesting
21 future directions. A mixed method review was employed to firstly identify highly relevant literature
22 using bibliometric search. The identified references were then analysed using qualitative content
23 analysis through the lens of I4.0 and I5.0. Results highlight several interactions between identified lean-
24 OSC tools and concepts, and I4.0 and I5.0 design principles, signifying the power of these
25 tools/concepts in meeting multiple industry objectives. The review also identifies significant overlap
26 between resilience principle in I5.0 and many of I4.0 principles, emphasising resilience as an integrative
27 concept of technological principles. Finally, several research gaps relating to the social and
28 environmental aspects of lean-OSC research were identified, including research on mental health,
29 assistive technologies, and design for end-of-life.

30 **Author Keywords:** Off-site construction; Lean manufacturing; Industry 4.0; Industry 5.0; Bibliometric
31 search; Mixed method review.

32 **Practical Applications**

33 Practitioners can benefit from understanding the capabilities of lean-OSC tools, such as process
34 simulation and BIM, in addressing a wide range of design principles of I4.0 and I5.0. This
35 paper also identifies the importance of exploring underexplored themes in the literature,
36 particularly the mental health of workers in off-site construction environments. As the industry
37 continues to evolve, construction professionals should consider incorporating new technologies
38 and methodologies to monitor and support the mental well-being of their workforce. There is
39 significant potential for improvement in adopting human-centred technologies, like
40 collaborative robots and exoskeletons, which can empower workers and enhance workplace
41 diversity and inclusion. This involves exploring innovative technologies that facilitate cross-
42 lingual communication, gestures recognition, and intention prediction, providing opportunities
43 for individuals with different languages, education levels, and disabilities to participate
44 effectively. Furthermore, the research highlights the need to concentrate on environmental
45 sustainability, specifically the integration of circular economy concepts into off-site
46 construction practices. By examining the potential of lean principles in promoting end-of-life
47 design considerations, such as design for disassembly and material passports, construction
48 professionals can bridge the gap between OSC and circular economy concepts, creating a more
49 sustainable construction industry.

50 **Introduction**

51 The construction industry has long been identified with the need to improve its productivity
52 and performance. One major attribute behind the lack of industrial growth is the traditional
53 stick-built approach, which is characterised with low standardisation, high fragmentation, and
54 limited automation (Li et al. 2014). These inefficiencies are not only associated with economic
55 disadvantages, but also with significant environmental impacts. For instance, the industry

56 contributes globally 40% solid waste (Oluleye et al. 2022), 33% greenhouse gasses emissions,
57 and 40% energy consumption (Ouldboukhitine et al. 2011).

58 In response, various governments promotes the adoption of off-site construction (OSC) as a
59 more sustainable building technique with promising capabilities to enhance productivity and
60 reduce environmental footprints (Jin et al. 2018). Typically, it involves the production of
61 building modules as components (e.g., wall panels or pods) in a factory setting before they are
62 transported to construction sites for installation (Goodier and Gibb 2007). The factory
63 production environment in OSC has long motivated academics and practitioners to apply
64 proven manufacturing techniques to increase productivity and profitability. OSC is suggested
65 to create several economic, social, and environmental benefits, including reduced construction
66 time (Mostafa et al. 2016), improved building quality (Zabihi et al. 2013), enhanced health and
67 safety (Mohandes et al. 2022), reduced construction waste (Mirshekarlou et al. 2021),
68 improved resource utilisation (Kedir and Hall 2021), and decreased carbon emissions (Wang
69 et al. 2022).

70 Lean manufacturing is a major production philosophy, originally developed by Toyota for
71 automobile production (Ohno and Bodek 1988). The main objective of lean philosophy is to
72 maximise customer value while reducing waste (Lean Enterprise Institute 2022). Given its
73 significant potential to improve efficiency and reduce waste, there is a growing body of
74 research employing lean principles to enhance OSC operations. This includes the use of just-
75 in-time (JIT) to optimise production efficiency (Afifi et al. 2020), visual management to
76 monitor and control the assembly process (Ma and Qiao 2021), Kaizen (i.e. continuous
77 improvement through measures adopting lean principles such as understanding customers,
78 empowering people and keeping the system transparent, etc.) to improve manufacturing
79 productivity (Darwish et al. 2020), and value stream mapping (VSM) to reduce lead times
80 (Zhang et al. 2020).

81 While majority of literature on lean off-site construction or lean manufacturing in off-site
82 construction (referred as 'lean-OSC' hereafter) emphasises the economic benefits, there are
83 relatively fewer studies focus on the wider social and environmental implications of lean-OSC.
84 Some researchers attribute this imbalance to the over-emphasis of the use of digital technology
85 in achieving economic gains as the industry is going through the fourth phase of industrial
86 revolution, i.e. Industry 4.0 (I4.0) (Xu et al. 2021). Recently, a new phase known as Industry
87 5.0 (I5.0) was proposed in attempt to steer a balance by focusing on wider social and
88 environmental benefits that go beyond just growth and productivity (Breque et al. 2021). Given
89 the growing uptake of lean theory in OSC and the ever-evolving industry requirements, our
90 knowledge is limited on how the application of lean tools and concepts in OSC can contribute
91 to the realisation of I4.0 and I5.0 principles. The authors conducted a thorough search but could
92 not find any prior studies that evaluated the potentials of lean in OSC towards meeting I4.0 and
93 I5.0 principles, widely recognized as important targets for several economies around the globe.
94 This study aims to evaluate extant lean-OSC literature in the lens of I4.0 and I5.0
95 conceptualisations, identifying key literature themes and gaps, and suggesting direction for
96 future research. To realise the study aim, the design principles underlying I4.0 and I5.0 are
97 reviewed and summarised. These principles are then used for evaluating the lean-OSC
98 literature. A mixed method review is adopted comprising the use of a bibliometric search to
99 objectively identify the research networks in lean-OSC literature which act as the main input
100 to a qualitative content analysis to evaluate the literature from the perspective of I4.0 and I5.0
101 design principles.

102 There are several published reviews amongst existing OSC literature addressing different
103 aspects in theory and practice. This includes reviews on OSC environmental sustainability
104 (Chen et al. 2022; Kedir and Hall 2021; Li et al. 2022; Luo et al. 2021; Zairul 2021), structural
105 integrity (Ghayeb et al. 2020; Navaratnam et al. 2019; Thai et al. 2020; Ye et al. 2021), supply

106 chain management (Hu and Chong 2021; Hussein et al. 2021; Masood et al. 2022; Wang et al.
107 2019), health and safety (Nguyen et al. 2020; Vithanage et al. 2022), and digital technology
108 (Assaf et al. 2022; Pan et al. 2022; Pasco et al. 2022; Qi et al. 2021; Wang et al. 2020b).
109 Although these reviews offered comprehensive analysis on different sustainability dimensions,
110 such as carbon reduction, circularity, and safety, links to lean uptake in OSC were not clear.
111 Only few reviews focused on the interplay between OSC and lean principles, studying key
112 literature directions, such as system automation (Gusmao Brissi et al. 2022), process simulation
113 (Daniel and Oshodi 2022; Mostafa et al. 2016), lean applicability (Du et al. 2023; Innella et al.
114 2019), and critical success factors (Hussein and Zayed 2021). However, these reviews have not
115 fully addressed the theoretical dimensions of I4.0 and 5.0, leaving a theoretical void that
116 requires scholarly attention. That is, little is known on how lean tools and concepts can facilitate
117 the realisation of I4.0 or I5.0 design principles in OSC. Furthermore, these reviews mostly
118 adopted a manual approach in selecting relevant references. While they all have a clear set of
119 selection criteria for selecting articles that allows the authors to study the contents of articles
120 in-depth according to their angle adopted for evaluation, there is an element of subjectivity for
121 interpretation of their criteria used, which can be prone to selectivity and lack of replicability
122 (Hammersley 2001). Improving from the previous reviews, this study employs a mixed method
123 attempting to benefit from the quantitative powers offered by the adopted bibliometric search
124 to shield potential authors' selectivity as well as an in-depth qualitative content analysis. Thus,
125 the literature analysis and evaluation are arguably more objective (see Hosseini et al., 2018).
126 Moreover, our study is limited to reviewing empirical studies, which are accentuated by several
127 scholars (e.g., Bhamu and Sangwan, 2014) to enhance the theoretical base of reviews.

128 This review contributes to existing body of knowledge in several ways. First, it informs OSC
129 theory and practice with the capabilities of applied lean tools and concepts in fulfilling different
130 industry requirements, including technological, economic, social, and environmental. In

131 addition, our study identifies key research gaps extant lean-OSC literature did not address fully
132 in the light of I4.0 and I5.0 design principles. In doing so, significant research directions are
133 suggested for future research to address.

134 **Industry 4.0 & 5.0 design principles**

135 Coined in 2011 by the German Federal government as part of a technological strategy, I4.0
136 theorised the reliance on Cyber Physical Production Systems (CPPSs) (Vogel-Heuser and Hess
137 2016). CPPSs offer smart and timely decisions communicated across the production
138 infrastructure (Lu et al. 2020), leading to significant improvements in product quality, process
139 lead times, and production efficiency (Zhong et al. 2017). To achieve I4.0, there are design
140 principles identified to enable manufacturers to conceive the transformative trends in the
141 industry and update their strategies accordingly (Ghobakhloo 2020). The most prevalent
142 categorisation to I4.0 design principles across the literature includes interoperability,
143 virtualisation, decentralisation, real-time capability, service orientation, and modularity (Koh
144 et al. 2019; Lu 2017; Mrugalska and Wyrwicka 2017; Oztemel and Gursev 2020; Shafiq et al.
145 2015, 2016; Wulfsberg 2017).

146 Although a few studies mentioned additional I4.0 design principles to address social and
147 environmental issues, such as social responsibility (Ghobakhloo 2018) and resource efficiency
148 (Kagermann et al. 2013), I4.0 is criticised for putting excessive focus on technologies to realise
149 economic gains (Xu et al. 2021). The technology driven transformations brought by I4.0 is
150 blamed for limiting human intervention (Demir et al. 2019; Lasi et al. 2014) and
151 overshadowing environmental protection principles (Maddikunta et al. 2022).

152 In response, I5.0 has been recently introduced with the aim of achieving wider production value
153 beyond growth and profitability (Breque et al. 2021). The European Commission through its
154 Directorate-General for Research and Innovation formally presented the concept in 2021 (Xu

155 et al. 2021). According to the European Commission, “*industry 5.0 recognises the power of*
156 *industry to achieve societal goals beyond jobs and growth to become a resilient provider of*
157 *prosperity, by making production respect the boundaries of our planet and placing the*
158 *wellbeing of the industry worker at the centre of the production process*” (Breque et al., 2021;
159 p.14). I5.0 therefore prioritises human-centricity, environmental sustainability, and resilience
160 as major design principles. I5.0, however, shall not be seen as a chronological continuation of
161 I4.0 (Xu et al. 2021). Rather, it is viewed as a complementary concept, emphasising wider
162 social and environmental implications (Breque et al. 2021). Table 1 summarises the definition
163 for each of I4.0 and I5.0 design principles. This study adopts those design principles as a
164 theoretical lens to evaluate lean-OSC literature later in this paper (see Qualitative Evaluation
165 Section).

166 ----- insert Table 1 here -----

167 **Methodology**

168 The aim of this study is to evaluate lean-OSC literature through the lens of I4.0 and I5.0 design
169 principles, identifying major literature themes and gaps, and suggesting future research
170 direction. To achieve this aim, a mixed method review was pursued starting with quantitative
171 bibliometric search to identify extant lean-OSC literature, followed by a qualitative content
172 analysis to evaluate identified studies from I4.0 and I5.0 perspectives. The bibliometric
173 approach provides objective criteria to identify the literature, through which the qualitative
174 approach goes on to offer more detailed synthesis on the relations, connections, and gaps
175 (Harden and Thomas 2015).

176 Two major keywords were used in the bibliometric search, namely: *off-site construction* and
177 *lean*. Interchangeable, synonymous, and related terms for the major keywords were identified
178 to make sure that the search is as comprehensive as possible. Upon reviewing key reviews in

179 the field (e.g., Jin et al., 2018; Yin et al., 2019), a range of synonymous and associated
180 keywords were identified and included in the search term as shown in Table 2.

181 ----- insert Table 2 here -----

182 Scopus database was chosen to search the articles for the analysis as it covers a wide range of
183 research publications (Chadegani et al. 2013; Darko et al. 2020), particularly in the field of
184 construction management (Hosseini et al. 2018; Yin et al. 2019). Based on the keywords
185 defined in Table 2, 586 articles were firstly retrieved. They were further reduced to 394 after
186 1) filtering out research in languages other than English, 2) excluding irrelevant subjects (e.g.
187 medicine, agriculture), 3) excluding reviews and 4) setting the search period to the last 15 years
188 - as I4.0 was introduced in 2011 and there is a notable drop in the number of publications
189 relevant to the keywords in 2007 and before (See Figure 1).

190 ----- insert Figure 1 here -----

191 Bibliometric search (introduced in the next section) was then employed to identify research
192 networks in the field of lean-OSC. The analysis identified one major research network and
193 eight minor ones, totalling 98 publications out of the 394 identified studies in the manual
194 search. Content analysis, introduced in the Quantitative Evaluation Section, was then
195 performed to firstly identify highly relevant papers to the study aim, bringing the total number
196 of publications down to 61. Theoretical and opinion-based articles were mostly excluded while
197 more focus was given to empirical research to ensure that our findings are based on evidence
198 rather than abstract theories. This is followed by literature evaluation to assess the 61
199 publications in the lens of I4.0 and I5.0 design principles. Figure 2 summarises the research
200 design pursued in this paper.

201 ----- insert Figure 2 here -----

202 **Bibliometric search**

203 VOSviewer was adopted for the bibliometric search as a widely utilised software and as an
204 efficient distance-based visualisation tool for research authorship, sources, keywords, and
205 articles compared to other bibliometric analysis tools, such as CiteSpace and CiteNetExplorer
206 (Yin et al. 2019). However, the adopted bibliometric search in this study is not meant to analyse
207 the retrieved literature sample (the 394 articles) in terms of their bibliometric information (e.g.,
208 authors, countries, trends). Instead, it is intended to objectively identify the research networks
209 in the field of lean-OSC and so providing content analysis with highly relevant studies to be
210 evaluated from I4.0 and I5.0 perspectives.

211 Particularly, articles citation analysis is adopted to 1) help identify lean-OSC research networks
212 more precisely based on relevant citations of recent articles to former ones; and 2) exclude
213 irrelevant and low quality/contribution papers which typically appear isolated with no single
214 link (i.e., citation) to the networks. We did not use bibliographic coupling analysis since it
215 prioritises research based on shared citations across the retrieved literature sample (i.e., the 394
216 articles) (Van Eck and Waltman 2021), no matter their relevance or contribution to the research
217 niche. In addition, threshold setting at bibliographic coupling analysis is arbitrary, based on
218 mutual citations that can lead to potential exclusion of relevant research. Therefore, a lower
219 threshold is preferred but considered impractical due to the significant number of research that
220 typically results in, requiring excessive screening effort. By contrast, at articles citation
221 analysis, a threshold of zero citations can be adopted to include all relevant research to the
222 research niche.

223 Based on articles citation analysis, the data of the 394 publications, initially mined from Scopus
224 database (see Method Section), was fed into VOSviewer. A threshold of zero citations was set,
225 since the main value of using the bibliometric search in this study is to identify the research
226 networks, not the most significant publications. This threshold then allowed including

227 potentially recent publications that have not yet received citations but cited previous work in
228 the networks. VOSviewer afterwards identified one major research network with 79
229 publications (Figure 3) and eight minor networks with 2-4 publications each (Figure 4). In total,
230 VOSviewer visualised 98 publications in all networks, while the rest of the 394 publications
231 appeared isolated, signifying potential irrelevance or limited contribution to lean-OSC
232 research. The authors investigated filtered research and found that a significant number of
233 articles was irrelevant, initially included because of keywords similarity to other disciplines
234 (e.g., computer science, astronomy). In comparison, fewer excluded studies are found to be
235 relevant. Although these studies received citations in general, they fail to receive or make a
236 single citation to the research network that is highly relevant to the research niche. As a result,
237 this research appeared isolated, without any connection to the VOSviewer research networks.
238 Although the content of the research may seem relevant, we considered it to have a low
239 contribution because it is not well embedded in the literature under investigation. Hence, the
240 value of these networks is to filter out less relevant studies to the research aim, allowing us to
241 focus further qualitative analysis on more relevant and coherent body of research.

242 ----- insert Figure 3 here -----

243 Figures 3 illustrates the biggest network of identified research (79 publications) in the field of
244 lean-OSC using VOSviewer articles citation analysis. Minor networks of such studies were
245 also identified (19 publications) as shown in Figure 4. The size of the node represents the
246 number of total citations received by each publication (in general). The bigger the node is, the
247 more citations received by the study. The links between nodes indicate the citations of recent
248 studies to former articles. The more links connected to a single node, the more relevant citations
249 are made to the given study in that node. The main purpose of this study is to evaluate the
250 literature from I4.0 and I5.0 perspectives, not to define literature themes and patterns. The
251 major function of the bibliometric search is to identify lean-OSC research networks (i.e.,

252 connected by citations) and so provide content analysis with an objectively identified literature
253 sample to be evaluated in the lens of I4.0 and I5.0 design principles.

254 ----- insert Figure 4 here -----

255 **Qualitative evaluation in lens of I4.0 & I5.0**

256 Content analysis was then employed to identify and analyse the most significant studies to the
257 research aim. As clarified in the Method Section, only empirical studies are selected for further
258 analysis, while theoretical and opinion-based studies are excluded to ensure that our review is
259 based on evidence, rather than theories. The number of studies was therefore reduced down to
260 61 articles (see the Appendix), as a major input for literature evaluation. Based on the
261 definitions introduced earlier in this review, literature evaluation in the lens of I4.0 & I5.0
262 design principles were performed as outlined in the below subsections.

263 *Interoperability*

264 The Internet of things (IoT) is the key enabling technology underpinning I4.0. One challenge
265 for IoT to operate efficiently and effectively is the need for systems to exchange, integrate and
266 use information seamlessly or in other words, systems need to be interoperable.
267 Interoperability, thus, refers to the ability of different systems to exchange, integrate, and utilise
268 data to enhance information sharing and exchange (Lu 2017).

269 Interoperability can be classified in four progressive levels (Van Der Veer and Wiles 2008),
270 they are: 1) technical, to establish required infrastructure to share raw data, 2) syntactic, to
271 share compatible data and offer minimal interpretation, 3) semantic, to exchange and interpret
272 data to create shared meaning, 4) organisational, to share higher level of knowledge reflecting
273 the efficiency of inter-organisational communications. The literature has mainly focused on
274 syntactic and organisational levels.

275 For *syntactic interoperability*, several studies employed optimisation methods to orchestrate
276 schedule trade-offs between the factory and the site, synchronising and prioritising data of
277 several variables, including the selection of suppliers (Zhang and Yu 2020), late/early delivery
278 penalties (Kong et al. 2018), and risk-related rescheduling options (Du et al. 2022). Other
279 studies adopted cross process simulations to integrate information of different processes to
280 optimise total time and cost (Heravi et al. 2021), carbon emissions (Heravi et al. 2020), and
281 digitalisation efficiency (Barkokebas et al. 2021a). Further, takt planning is employed to
282 synchronise production information necessary to smooth resource utilisation (Chauhan et al.
283 2018), and reduce delays (Lerche et al. 2022). Other studies adopted Design for Manufacture
284 and Assembly (DfMA) principles to synchronise design information with manufacturing and
285 assembly processes to verify design geometry prior to production (He et al. 2021), and improve
286 site safety and logistics efficiency (Banks et al. 2018). Therefore, these studies do not go
287 beyond syntactic interoperability, failing to develop ontology-based systems, similar to those
288 found in non-lean OSC literature on cost estimation (Vakaj et al. 2023) and manufacturability
289 (Cao et al. 2022).

290 For *organisational interoperability*, several studies employed 4D BIM, a schedule visualisation
291 tool integrating schedule and design information, to coordinate logistics and assembly activities
292 among different project participants (Bortolini et al. 2019). Several benefits are reported by
293 this literature, including improvements in transportation reliability (Bataglin et al. 2020),
294 assembly control (Peñaloza et al. 2016), process transparency (Bataglin et al. 2017), and
295 schedule compliance (Wang et al. 2020a). Other studies developed a range mass customisation
296 platforms that promote design collaboration (Jansson et al. 2014) by integrating the
297 requirements of different stakeholders (Yazdi et al. 2020), particularly customer needs and
298 expectations (Viana et al. 2017).

299 *Virtualisation*

300 Virtualisation principle aims to digitise physical systems to predict and optimise performance
301 (Qi and Tao 2018). It can be classified to two categories 1) process level, to monitor and
302 optimise process activities without disrupting physical world (Gilchrist 2016), and 2) product
303 level, to have a holistic virtual view of a product from design to the end of life (Ghobakhloo
304 2018). For *process virtualisation*, several studies adopted process simulation techniques to
305 optimise specific production sub-processes based on the lean concept of VSM. Typically, VSM
306 is used to map and classify process activities into value adding, non-value adding, necessary
307 non-value adding activities (Nikakhtar et al. 2015), before eliminating non-value adding
308 activities (i.e., waste) to enhance process flow (Innella et al. 2019). Through process
309 simulations to map current state activities, potential improvements are identified to enhance
310 manufacturing productivity (Yu et al. 2013; Zhang et al. 2020), decrease lead times (Laika et
311 al., 2022), optimise resource utilisation (Goh and Goh 2019), minimise cost (Heravi and Firoozi
312 2017; Laika et al. 2022), and reduce process waste (Ayinla et al., 2022; El Sakka et al., 2016).
313 Other studies approached process virtualisation using simulations of workers motion and
314 interaction primarily to reduce health and safety hazards. This includes the use of rapid entire
315 body assessment (Ritter et al. 2019), and rapid upper limb assessment (Barkokebas et al. 2021b)
316 to evaluate ergonomic risks and in turn enhance OSC health and safety conditions.

317 For *product virtualisation*, literature investigations approached it primarily in two different
318 ways. The first involves the use of BIM to visualise progress in building construction (e.g.,
319 Bataglin et al., 2020; Peñaloza et al., 2016), facilitate module production (He et al. 2021), and
320 optimise module assembly (Gbadamosi et al. 2019). Other studies adopted life cycle
321 assessment (LCA) to estimate the environmental impacts of prefabricated components (Heravi
322 et al. 2020) and their assembly stations (Kurdve et al. 2018). The importance of estimating the

323 environmental impacts of OSC modules lies on the capability to control the footprint of
324 contributing processes (e.g., production, logistics).

325 *Decentralisation*

326 The decentralisation principle aims to enable stakeholders and information systems to analyse
327 data and take decisions independently in pursuit of common organisational objectives
328 (Gilchrist 2016). The literature on decentralisation can be classified into 1) autonomous teams
329 and 2) autonomous systems. For *autonomous teams*, several studies (e.g., Bataglin et al., 2020;
330 Bortolini et al., 2019; Peñaloza et al., 2016) adopted Last Planner System (LPS) to achieve
331 efficient delegation and collaboration in the planning and control of OSC operations. LPS is
332 centred on the empowerment of people involved in planning and implementation of daily
333 activities (Lean Construction Institute 2022).

334 For *autonomous systems*, several studies focused on developing optimisation-based models to
335 facilitate decision making by optimising different supply chain variables, such as level of
336 components modularity (Isaac et al. 2014), production sequencing (Arashpour et al. 2016), and
337 logistics operations (Zhang and Yu 2020). Hu et al. (2021) hold that the quality of problem
338 formulation highly influences the capability of optimisation models to establish a fully
339 optimised and automated systems. Other studies used mass customisation platforms to promote
340 design automation by identifying advanced capabilities to support handling unique designs
341 (Jansson et al. 2014), defining rules and constraints for automated modules connections
342 (Thajudeen et al. 2020), and adapting suppliers' processes to platform requirements (Yazdi et
343 al. 2020).

344 *Real-time capability*

345 Real-time capability refers to the quality in collecting, sharing, and interpreting data to assist
346 timely decision making (Hermann et al. 2016). Based on literature analysis, three categories
347 can be identified: design integration, production monitoring, and logistics tracking & control.
348 Regarding *design integration*, BIM models form a reliable reference for decision making
349 throughout construction lifecycle (National BIM Standard 2022). They can be integrated to
350 other systems to verify production geometry (He et al. 2021) and develop mass-customisation
351 platform (Thajudeen et al. 2020). For *production monitoring*, real-time process simulation is
352 adopted using continuous event simulation to monitor production performance and device
353 improvements in productivity (Afifi et al. 2020) and long-term efficiency (Arashpour et al.
354 2015). Real-time production monitoring systems facilitate proactive detection of process waste
355 and so stimulate timely mitigating decisions (Snatkin et al. 2013). Other studies used the lean
356 concept of takt planning to synchronise production rhythm with actual market demand,
357 reporting several benefits including resource optimisation (Chauhan et al. 2018) and
358 productivity improvements (Lerche et al. 2022). For *logistics tracking & control*, component
359 level data (e.g., location and class) are synchronised in real-time using module tracking
360 technologies, such as RFID and IoT to optimise logistics cost and efficiency (Wang et al.
361 2020a), and support on-time deliveries (Xu et al. 2018).

362 *Service orientation*

363 This principle aims to focus intelligent production systems on meeting or exceeding customer's
364 needs and expectations (Kamble et al. 2018). The literature addressing this principle can be
365 classified to production process and design process. The major portion of these studies focused
366 on the *production process* using the concept of VSM to maximise customer value. Several
367 studies (e.g., Heravi and Firoozi, 2017; Zhang et al., 2020) employed the lean concept of VSM
368 with process simulation mainly to fast-track delivery by reducing lead times. Integrating VSM

369 with discrete event simulations are widely advocated to model variability in customer demand,
370 which otherwise the VSM per se is unable to model (Jarkko et al. 2013) due to its deterministic
371 nature (Hampson 1999). Other studies adopted the lean concept of takt planning to match the
372 production pace with actual customer demand and so promote resource efficiency and
373 eliminate wasteful activities (Chauhan et al. 2018; Lerche et al. 2022).

374 Other studies (Jansson et al. 2014; Thajudeen et al. 2020; Viana et al. 2017; Yazdi et al. 2020)
375 focus on the potentials of the *design process* in satisfying customer needs and expectation using
376 mass customisation platforms. Mass customisation refers to the capability to deliver products
377 that meet customers personalisation needs at mass production efficiency (MacCarthy et al.
378 2003). Hence, it attempts to realise two apparently conflicting objectives of high product
379 variety and high volume (Viana et al. 2017). This capability is underpinned by two lean
380 concepts: batch size reduction to promote design modularisation by dividing the building
381 design into smaller common modules (Hopp and Spearman 2004), and standardisation to
382 consolidate module design with the aim of realising mass production efficiency (Liker 2020).

383 *Modularity*

384 This principle enables supply chain to adopt agile mindset in responding to rapidly changing
385 market conditions (Ghobakhloo 2018). Based on the analysed literature, two major categories
386 are identified, namely product-based and process-based modularity, both concentrating on
387 breaking the major module/system into smaller manageable units (Koh et al. 2019). Focusing
388 on *product modularity*, several studies (Choi et al. 2020; Feist et al. 2022; O'Connor et al.
389 2015; Økland et al. 2017, 2018; Viana et al. 2017) adopted design modularisation to enhance
390 post-design modules identification (Feist et al. 2022), decrease cost, delays and defects (Økland
391 et al. 2017, 2018), and reduce complexity in engineer-to-order projects (Viana et al. 2017).
392 Other studies focused on DfMA aiming at product design simplification and integration to

393 enhance manufacturability and constructability (Leminen et al. 2013). This includes the
394 development of design modularisation tools to assess module design based on the level of
395 modularity, standardisation, producibility, and assemblability (Antoniou and Marinelli 2020;
396 Gbadamosi et al. 2019).

397 Several other studies focused on *process modularity*, with primary adoption of process
398 simulation to map and optimise specific production processes. Applying the lean concepts,
399 these studies demonstrate a range of benefits in productivity (Yu et al. 2013), lead time (Heravi
400 and Firoozi 2017), and resource efficiency (El Sakka et al. 2016). In addition, there are studies
401 adopting the concept of flying factories to physically modularise specific production activities
402 on site (He et al. 2021; Martínez et al. 2013; Rosarius and García De Soto 2021), demonstrating
403 a number of economic, social, and environmental benefits.

404 *Human centricity*

405 This principle involves prioritising workers' needs and interests over growth and profitability
406 brought by emergent technologies (Nahavandi 2019). The *empowerment of people* is identified
407 as the major aspect emphasised by this literature, mainly underpinned by the lean concept
408 Kaizen, to eliminate process waste (El Sakka et al. 2016), boost productivity (Afifi et al. 2020),
409 and reduce lead times (Barkokebas et al. 2021a). Kaizen refers to the labour-led continuous
410 improvement mindset to remove waste and enhance process efficiency (Nahmens and Ikuma
411 2012). Other studies suggest cross-training to expand multi-skilled labour, reporting
412 improvements in changeover times (Arashpour et al. 2016), labour utilisation, and productivity
413 (Arashpour et al. 2017; Goh and Goh 2019). Multi-skilled workers, for instance, can improve
414 production flexibility by addressing potential variabilities in resource availability and customer
415 demand (Alvanchi et al. 2012). Andersen et al. (2008) suggest the social infrastructure (e.g.,
416 shared vision & internal coherence) underpinning OSC production culture as a prerequisite for

417 successful manufacturing environment. This view is reinforced by Alazzaz and Whyte (2015)
418 who revealed a significant positive correlation between labour empowerment and productivity
419 in OSC.

420 Labours' *health and safety* is another aspect researched by several studies, using a range of
421 tools and techniques. I5.0 introduces workers' health and safety as an essential requirement,
422 aiming at enhancing physical health, mental health, and wellbeing (Xu et al. 2021). Relevant
423 literature includes the adoption of Kaizen to encourage workers' led safety improvements
424 (Nahmens and Ikuma 2012), ergonomic risk assessment to evaluate proposed process
425 improvements (Barkokebas et al. 2021b; Ritter et al. 2019), and JIT to reduce site hazards
426 related excess inventory (Court et al. 2009).

427 There are studies promoted *wider social implications* to OSC, as a core tenet of I5.0, which
428 postulates that technology has to be designed to serve the wider community, not the opposite
429 (Breque et al. 2021). Particularly, employment prospects are promoted by some studies
430 adopting the development of less skill-demanding production technologies based on the lean
431 concept of poka-yoke (i.e., error proofing) to enhance the quality and safety of manual
432 assembly activities (Kurdve 2018; Kurdve et al. 2018). Likewise, flying factories are being
433 recommended as an efficient way to enhance local labour employment, combining the
434 advantages of off-site and on-site construction (Li et al. 2020).

435 *Environmental sustainability*

436 Sustainability principle aims to reduce waste, minimise environmental impacts, and promote
437 circular manufacturing principles (Rada 2018). The analysis reveals three major interrelated
438 foci under this principle, including waste reduction, emissions cut, and circularity promotion.
439 For *waste reduction*, a significant number of studies adopt process simulations to reduce
440 process waste, including the reduction of overproduced modules (El Sakka et al. 2016), lead

441 times (Heravi and Firoozi 2017), and work-in-progress levels (Goh and Goh 2019). Process
442 waste refers to the excess amount of production resources that do not add customer value
443 (Ayinla et al., 2022). These waste are directly and indirectly linked to the generation of solid
444 waste, which creates negative environmental impacts (Nahmens and Ikuma 2012). Several
445 studies identified the potential of OSC in reducing material waste by improving production
446 accuracy (He et al. 2021), optimising design to facilitate assembly (Gbadamosi et al. 2019),
447 and devising process improvement to reduce off-cuts (Nahmens and Ikuma 2012).

448 For *emissions reduction*, several studies promoted reducing logistics emissions resulting from
449 transporting building modules from OSC facilities to the site. This includes literature adopting
450 JIT to optimise transportation time and quantity (Kong et al. 2018), DfMA to enhance
451 transportation efficiency (Banks et al. 2018), and flying factories to eliminate factory-to-site
452 transportation (He et al. 2021). Other studies employed LCA to estimate material emissions as
453 a result of raw materials' extraction, transportation, processing, construction, renovation,
454 maintenance, deconstruction, and disposal, i.e. their embodied carbon emissions. Kurdve et al.
455 (2018), in a case study, adopted LCA to carry out emissions hotspot analysis that assist
456 designers to choose environmentally friendly materials in early design stage.

457 Mignacca and Locatelli (2021) stress the need to overcome barriers in the face of modular
458 circular economy which involves the building strategy where prefabricated modules are
459 designed to be reused, maintained, altered, and recycled (Mignacca et al. 2020). For *circularity*
460 *promotion*, the literature focused on the reuse of shipping containers in construction as building
461 modules. This includes the work Giriunas et al. (2012) who investigated the structural
462 capabilities of shipping containers using finite element analysis, producing a structural
463 guidelines for reuse in construction. Relatedly, Su et al. (2022) used BIM to integrate data on
464 shipping containers and traditional construction modules to promote their reuse in construction.
465 The reutilisation of shipping containers in construction is gaining popularity as a modular

466 circular building technique, e.g., the Stadium 974 project in Qatar that uses 974 recycled
467 shipping containers to build a football stadium.

468 *Resilience*

469 This principle aims to establish higher levels of production robustness mainly to withstand
470 potential supply chain disruptions (Breque et al. 2021). Ekanayake's et al. (2020) define nine
471 components for OSC supply chain resilience, including resourcefulness, flexibility, capacity,
472 adaptability, efficiency, financial strength, visibility, anticipation, and dispersion. The authors
473 also identify a range of supporting traits for each component (see Table 6). Most of those traits
474 are arguably applied to some of the I4.0 design principles, e.g. “collaborative information
475 exchange and decision making” for interoperability, “modular product design” for modularity,
476 “products, assets, people visibility” for virtualisation, “monitoring early warning signals” and
477 real-time capability, and “distributed decision making” for decentralisation.

478 Other studies promoted several resilience traits in different components with no direct link to
479 I4.0 design principles. For example, studies promoting OSC health & safety (e.g., Barkokebas
480 et al., 2021b) supported “resourcefulness” component since they aim to reduce disruptions
481 related to labour health & safety (Ekanayake et al. 2020). Likewise, studies adopting JIT (e.g.,
482 Kong et al., 2018) and standardisation (e.g., Antoniou and Marinelli, 2020) supported
483 “flexibility” component, since they both facilitate timely and efficient resource mobilisation
484 (see Ekanayake et al., 2020) by producing only what is needed when needed and allow
485 repetitive use of resources. Other studies supported “adaptability” by promoting lead time
486 reduction (e.g., Zhang et al., 2020), which enhances supply chain capability to adapt in
487 response to disruptions (Ekanayake et al. 2020). Moreover, several studies supported
488 “efficiency” component by promoting OSC resources optimisation and waste elimination
489 (Ekanayake et al. 2020). This includes studies promoting rework reduction (El Sakka et al.

490 2016), productivity increase (Afifi et al. 2020), waste elimination (Ayinla et al., 2022), failure
491 prevention (Heravi et al. 2021), and learning from experience (Antoniou and Marinelli 2020).
492 Finally, “anticipation” component is supported by studies addressing cross-training (Goh and
493 Goh, 2019), which involve fostering workers’ capabilities to detect and mitigate potential
494 inefficiencies that could disrupt future operations (Ekanayake et al. 2020). This study, however,
495 finds that the two resilience components, capacity and financial strength, are not well studied
496 in previous literature. Table 3 summarises the lean-OSC literature that addresses the resilience
497 components.

498 ----- insert Table 3 here -----

499 **Discussion**

500 Upon analysing the literature, several lean tools and concepts were identified and linked to the
501 realisation of different Industry 4.0 and 5.0 design principles in OSC. These tools and concepts
502 may be termed as “lean-OSC tools and concepts”. Figure 5 illustrates these tools and concepts
503 and their support to the identified literature themes. The number of connections (stated as a
504 number between parenthesis) reflects the frequency of support to different themes. Several
505 lean-OSC tools and concepts supported multiple literature themes, highlighting their power in
506 meeting the objectives of different design principles. Particularly, *process simulation* and *BIM*
507 were the most supporting lean-OSC tools to meet a wide range of I4.0 & I5.0 design principles.
508 This suggests the need to have a broad vision in applying the tools or concepts to maximise the
509 potential of meeting I4.0 and I5.0. For instance, the application of process simulation can be
510 extended beyond process virtualisation, by considering potential environmental benefits
511 process simulation can bring (e.g., waste elimination).

512 One interesting observation in this review is on *resilience principle*, which reveals similarities
513 with several I4.0 design principles, including virtualisation, decentralisation, real-time

514 capability, interoperability, and modularity. That is, reviewing lean-OSC literature from the
515 perspective of resilience principle, as per Ekanayake et al (2020) explanation, reveals several
516 commonalities. This suggests resilience as an overarching principle aiming at employing I4.0
517 principles to design efficient production systems that can weather potential supply chain
518 disruptions. However, gaps can be identified in the literature with no study identified to address
519 the resilience components of “capacity” and “financial strength”, which have a common
520 purpose on determining the level of manufacturers’ preparedness and power to avoid
521 disruptions (Ekanayake et al. 2020).

522 For human centricity, several themes have been addressed in previous literature, including
523 health and safety, empowerment of people, and wider social implications. However, comparing
524 these themes with the enabling technologies for I5.0 as defined by the European Commission
525 (see Müller, 2020) reveals several gaps. For health and safety, lean-OSC literature focused on
526 mitigating ergonomic risk – which is mainly related to the physical impacts, whereas attention
527 is not paid to the impacts on mental health. Employing technology to monitor labour mental
528 health is of crucial importance amid ever increasing popularity of construction
529 industrialisation. For empowerment of people, the literature focused on labour-led process
530 improvements (i.e., Kaizen) and cross-training, with a lack of studies on the application of
531 other emerging technologies, such as collaborative robots and exoskeletons. The main notion
532 behind these technologies is to support human roles by integrating human powers with
533 technological capabilities (Müller, 2020).

534 For wider social implications, there are extant research focused on enhancing employment
535 prospects through introducing a range of less skills demanding roles (e.g., Kurdve et al., 2018).
536 However, studies on technologies facilitating cross-lingual communication, gestures
537 recognition, and intention prediction are lacking. The importance of these technologies lies on
538 their capability to enhance workplace diversity and inclusion, particularly by extending

539 employment opportunities to people of different languages, education, and disabilities (see
540 Müller, 2020).

541 For environmental sustainability, the focus of lean-OSC research is directed towards waste and
542 emission reduction with limited research on bridging circularity and lean-OSC in the umbrella
543 of Industry 5.0 (e.g., reusing shipping containers in construction). In this regard, there are no
544 lean-OSC empirical studies on *design for disassembly* and *material passport*. The former
545 involves early design decisions on material choices, module design, and joint selection to
546 facilitate materials recovery at the end of life (Bovea et al. 2016), while the latter concerns the
547 quality and quantity of materials used in products to give information about material recovery
548 at the end of life (BAMB 2020). Together, they give the potential opportunities for creating a
549 cradle-to-cradle circular economy.

550 Moreover, there are limited research examined the application of lean principles in mitigating
551 the environmental impacts in addition to wastage and emissions, e.g. on on-site construction
552 against the off-site alternatives. Several OSC activities in the construction site, such as
553 earthworks and foundations, still largely influenced by traditional construction practices. Such
554 practices are linked significant environmental impacts, such as soil contamination and
555 destruction of habitats (see Malik and Marathe, 2022).

556 ----- insert Figure 5 here -----

557 **Conclusions**

558 Identifying the state-of-the-art tools and concepts in the field of lean-OSC and understanding
559 their contribution to meeting the requirements of different I4.0 and I5.0 design principles have
560 seminal implications. First, the review informs OSC practice of the specific capabilities of
561 different lean-OSC tools and concepts in meeting technological, economic, social, and
562 environmental industry requirements. Further, our findings also provide OSC scholars with a

563 better picture on the unexplored themes, tools, and capabilities in fulfilling I4.0 and I5.0
564 objectives using lean concepts. This study is the first of its kind to evaluate lean-OSC research
565 from the perspective of I4.0 and I5.0 using a mixed method design.

566 The review also suggests several directions for future research. They are summarised below:

- 567 • Limited studies addressing the resilience components of "capacity" and "financial
568 strength," which determine manufacturers' preparedness and power to avoid
569 disruptions.
- 570 • Lean-OSC literature focuses on mitigating ergonomic risk but lacks attention on the
571 impacts on mental health.
- 572 • Limited studies on the application of emerging technologies, such as collaborative
573 robots and exoskeletons, to support human roles in the construction process.
- 574 • Research gaps in technologies facilitating cross-lingual communication, gestures
575 recognition, and intention prediction, which are crucial for enhancing workplace
576 diversity and inclusion.
- 577 • Lean-OSC research focuses on waste and emission reduction with limited research
578 bridging circularity and lean-OSC in the umbrella of Industry 5.0 and lack of empirical
579 studies on design for disassembly and material passport.
- 580 • Many on-site construction activities, such as earthworks and foundations, are still
581 influenced by traditional construction practices, which contribute to significant
582 environmental impacts.

583 **Appendix.** Analysed literature versus relevant I4.0 & I5.0 design principles.

Year	Authors	Title	Interoperability	Virtualisation	Decentralisation	Real-time capability	Service orientation	Modularity	Human-centricity	Envir. Sustainability	Resilience
2009	Court P.F., Pasquire C.L., Gibb G.F., Bower D.	Modular assembly with postponement to improve health, safety, and productivity in construction	✓						✓		✓
2012	Nahmens I., Ikuma L.H.	Effects of lean construction on sustainability of modular homebuilding							✓	✓	✓
2012	Han S.H., Al-Hussein M., Al-Jibouri S., Yu H.	Automated post-simulation visualization of modular building production assembly line		✓		✓	✓	✓			✓
2012	Giriunas K., Sezen H., Dupaix R.B.	Evaluation, modeling, and analysis of shipping container building structures		✓						✓	✓
2013	Martínez S., Jardón A., Víctores J.G., Balaguer C.	Flexible field factory for construction industry						✓		✓	✓
2013	Yu H., Al-Hussein M., Al-Jibouri S., Telyas A.	Lean transformation in a modular building company: A case for implementation		✓			✓	✓		✓	✓
2014	Isaac S., Bock T., Stoliar Y.	A new approach to building design modularization	✓		✓			✓			✓
2014	Jansson G., Johnsson H., Engström D.	Platform use in systems building			✓		✓	✓			✓
2015	Alazzaz F., Whyte A.	Linking employee empowerment with productivity in off-site construction							✓		✓
2015	Arashpour M., Wakefield R., Bliskas N., Maqsood T.	Autonomous production tracking for augmenting output in off-site construction		✓		✓		✓			✓
2015	O'Connor J.T., O'Brien W.J., Choi J.O.	Standardization strategy for modular industrial plants						✓			✓
2016	El Sakka F., Eid K., Narciss T., Hamzeh F.	Integrating lean into modular construction: A detailed case study of company X		✓			✓	✓	✓	✓	✓
2016	Arashpour M., Wakefield R., Abbasi B., Lee E.W.M., Minas J.	Off-site construction optimization: Sequencing multiple job classes with time constraints			✓				✓		✓
2016	Zhang Y., Fan G., Lei Z., Han S., Raimondi C., Al-Hussein M., Bouferguene A.	Lean-based diagnosis and improvement for offsite construction factory manufacturing facilities					✓		✓		
2016	Peñaloza G.A., Viana D.D., Bataglin F.S., Formoso C.T., Bulhões I.R.	Guidelines for integrated production control in engineer-to-order prefabricated concrete building systems: Preliminary results	✓	✓	✓	✓					✓

2017	Viana D.D., Tommelein I.D., Formoso C.T.	Using modularity to reduce complexity of industrialized building systems for mass customization					✓	✓			✓
2017	Heravi G., Firoozi M.	Production process improvement of buildings' prefabricated steel frames using value stream mapping		✓			✓	✓		✓	✓
2017	Arashpour M., Too E., Le T.	Improving productivity, workflow management, and resource utilization in precast construction							✓		✓
2017	Liu Y., Zhang X., Zhu F.	Analysis of Non-Value-Adding Activities in Prefabricated Building Construction Project: Case Study					✓				
2017	Kong L., Li H., Luo H., Lieyun D., Luo X., Skitmore M.	Optimal single-machine batch scheduling for the manufacture, transportation and JIT assembly of precast construction with changeover costs within due dates	✓		✓						✓
2017	Bataglin F.S., Viana D.D., Formoso C.T., Bulhões I.R.	Application of BIM for supporting decision-making related to logistics in prefabricated building systems	✓	✓	✓	✓					✓
2018	Økland A., Johansen A., Olsson N.O.E.	Shortening lead-time from project initiation to delivery: A study of quick school and prison capacity provision						✓			✓
2018	Banks C., Kotecha R., Curtis J., Dee C., Pitt N., Papworth R.	Enhancing high-rise residential construction through design for manufacture and assembly - A UK case study	✓						✓	✓	✓
2018	Kurdve M., Hildenbrand J., Jönsson C.	Design for green lean building module production - Case study		✓				✓	✓	✓	✓
2018	Chauhan K., Peltokorpi A., Seppänen O., Berghede K.	Combining takt planning with prefabrication for industrialized construction	✓			✓	✓				✓
2018	Xu G., Li M., Chen C.-H., Wei Y.	Cloud asset-enabled integrated IoT platform for lean prefabricated construction	✓	✓		✓				✓	✓
2018	Kong L., Li H., Luo H., Ding L., Zhang X.	Sustainable performance of just-in-time (JIT) management in time-dependent batch delivery scheduling of precast construction	✓		✓					✓	✓
2018	Wesz J.G.B., Formoso C.T., Tzortzopoulos P.	Planning and controlling design in engineered-to-order prefabricated building systems			✓						✓
2018	Minunno R., O'Grady T., Morrison G.M., Gruner R.L., Colling M.	Strategies for applying the circular economy to prefabricated buildings								✓	✓
2019	Gbadamosi A.-Q., Mahamadu A.-M., Oyedele L.O., Akinade O.O., Manu P., Mahdjoubi L., Aigbavboa C.	Offsite construction: Developing a BIM-Based optimizer for assembly		✓				✓		✓	✓
2019	Goh M., Goh Y.M.	Lean production theory-based simulation of modular construction processes		✓			✓	✓	✓	✓	✓
2019	Ritter C., Barkokebas R.D., Li X., Al-Hussein M.	Integrated ergonomic and productivity analysis for process improvement of panelised floor manufacturing		✓					✓		✓
2019	Ahmad S., Soetanto R., Goodier C.	Lean approach in precast concrete component production					✓				
2019	Bortolini R., Formoso C.T., Viana D.D.	Site logistics planning and control for engineer-to-order prefabricated building systems using BIM 4D modeling	✓	✓	✓	✓				✓	✓
2020	Antoniou F., Marinelli M.	Proposal for the Promotion of Standardization of Precast Beams in Highway Concrete Bridges						✓			✓
2020	Yazdi A.J., Fini A.A.F., Forsythe P.	An Integrated Product Planning and Design Platform in the Context of Housebuilding Industry	✓		✓		✓	✓			✓

2020	Thajudeen S., Lennartsson M., Elgh F., Persson P.J.	Parametric modelling of steel connectors in a glulam based post and beam building system - Towards a flexible product platform approach			✓	✓	✓	✓			✓
2020	Li L., Li Z., Li X., Zhang S., Luo X.	A new framework of industrialized construction in China: Towards on-site industrialization					✓	✓	✓	✓	✓
2020	Zhang Y., Lei Z., Han S., Bouferguene A., Al-Hussein M.	Process-Oriented Framework to Improve Modular and Offsite Construction Manufacturing Performance		✓			✓	✓		✓	✓
2020	Afifi M., Fotouh A., Al-Hussein M., Abourizk S.	Integrated lean concepts and continuous/discrete-event simulation to examine productivity improvement in door assembly-line for residential buildings		✓		✓		✓	✓	✓	✓
2020	Bataglin F.S., Viana D.D., Formoso C.T., Bulhões I.R.	Model for planning and controlling the delivery and assembly of engineer-to-order prefabricated building systems: Exploring synergies between lean and BIM	✓	✓	✓	✓					✓
2020	Wang M., Altaf M.S., Al-Hussein M., Ma Y.	Framework for an IoT-based shop floor material management system for panelized homebuilding	✓	✓		✓					✓
2020	Zhang H., Yu L.	Dynamic transportation planning for prefabricated component supply chain	✓		✓					✓	✓
2020	Heravi G., Rostami M., Kebria M.F.	Energy consumption and carbon emissions assessment of integrated production and erection of buildings' pre-fabricated steel frames using lean techniques	✓	✓			✓			✓	✓
2020	Choi J.O., Shrestha B.K., Kwak Y.H., Shane J.S.	Innovative Technologies and Management Approaches for Facility Design Standardization and Modularization of Capital Projects		✓				✓			✓
2021	He R., Li M., Gan V.J.L., Ma J.	BIM-enabled computerized design and digital fabrication of industrialized buildings: A case study	✓	✓		✓		✓		✓	✓
2021	Barkokebas R.D., Ritter C., Al-Hussein M., Li X.	Simulation-based decision support for production improvement using integrated ergonomic and productivity performance indicators		✓				✓	✓	✓	✓
2021	Lerche J., Neve H., Gross A., Wandahl S.	A MODEL TO LINK TAKT SCHEDULES AND OPERATIONS IN CONSTRUCTION	✓			✓	✓				✓
2021	Salama T., Salah A., Moselhi O.	Integrating critical chain project management with last planner system for linear scheduling of modular construction	✓	✓	✓	✓					✓
2021	Heravi G., Kebria M.F., Rostami M.	Integrating the production and the erection processes of pre-fabricated steel frames in building projects using phased lean management	✓	✓			✓			✓	✓
2021	Barkokebas B., Khalife S., Al-Hussein M., Hamzeh F.	A BIM-lean framework for digitalisation of premanufacturing phases in offsite construction	✓			✓	✓		✓	✓	✓
2021	Rosarius A., García De Soto B.	On-site factories to support lean principles and industrialized construction						✓	✓	✓	✓
2021	Ezzeddine A., García de Soto B.	Connecting teams in modular construction projects using game engine technology	✓	✓							✓
2021	Mignacca B., Locatelli G.	Modular Circular Economy in Energy Infrastructure Projects: Enabling Factors and Barriers		✓				✓		✓	✓
2022	Feist S., Sanhudo L., Esteves V., Pires M., Costa A.A.	Semi-Supervised Clustering for Architectural Modularisation	✓		✓			✓			✓
2022	Bao Z., Laovisutthichai V., Tan T., Wang Q., Lu W.	Design for manufacture and assembly (DfMA) enablers for offsite interior design and construction						✓			✓
2022	Ayinla K., Cheung F., Skitmore M.	Process Waste Analysis for Offsite Production Methods for House Construction: A Case Study of Factory Wall Panel Production		✓			✓	✓		✓	✓

2022	Laika M., Heravi G., Rostami M., Ahmadi S.	Improving the Performance of Precast Concrete Production Processes by Simultaneous Implementation of Lean Techniques and Root Cause Analysis		✓			✓	✓		✓	✓
2022	Lerche J., Enevoldsen P., Seppänen O.	Application of Takt and Kanban to Modular Wind Turbine Construction	✓			✓	✓				✓
2022	Du J., Xue Y., Sugumaran V., Hu M., Dong P.	Improved biogeography-based optimization algorithm for lean production scheduling of prefabricated components	✓		✓		✓				✓
2022	Su M, Yang B , and Wang X	Research on Integrated Design of Modular Steel Structure Container Buildings Based on BIM	✓	✓				✓		✓	✓

584

585

586

587

588

589

590

591

592

593

594 **Data availability statement**

595 All data, models, and code generated or used during the study appear in the submitted article.

596 **References**

597 Afifi, M., A. Fotouh, M. Al-Hussein, and S. Abourizk. 2020. “Integrated lean concepts and
598 continuous/discrete-event simulation to examine productivity improvement in door assembly-line
599 for residential buildings.” *Int. J. Constr. Manag.*
600 <https://doi.org/10.1080/15623599.2020.1793075>.

601 Alazzaz, F., and A. Whyte. 2015. “Linking employee empowerment with productivity in off-site
602 construction.” *Eng. Constr. Archit. Manag.*, 22 (1): 21–37. [https://doi.org/10.1108/ECAM-09-
603 2013-0083](https://doi.org/10.1108/ECAM-09-2013-0083).

604 Alvanchi, A., S. Lee, and S. M. AbouRizk. 2012. “Dynamics of workforce skill evolution in
605 construction projects.” *Can. J. Civ. Eng.*, 39 (9): 1005–1017. NRC Research Press.
606 <https://doi.org/https://doi.org/10.1139/l2012-087>.

607 Andersen, B., T. Bølviken, H. S. Dammerud, and S. Skinnarland. 2008. “Approaching construction as
608 a logistical, economical and social process.” *Proc. IGLC16 16th Annu. Conf. Int. Gr. Lean Constr.*,
609 27–38.

610 Antoniou, F., and M. Marinelli. 2020. “Proposal for the Promotion of Standardization of Precast Beams
611 in Highway Concrete Bridges.” *Front. Built Environ.*, 6.
612 <https://doi.org/10.3389/fbuil.2020.00119>.

613 Arashpour, M., E. Too, and T. Le. 2017. “Improving productivity, workflow management, and resource
614 utilization in precast construction.” *ISEC 2017 - 9th Int. Struct. Eng. Constr. Conf. Resilient Struct.
615 Sustain. Constr.*

616 Arashpour, M., R. Wakefield, B. Abbasi, E. W. M. Lee, and J. Minas. 2016. “Off-site construction
617 optimization: Sequencing multiple job classes with time constraints.” *Autom. Constr.*, 71 (Part 2):
618 262–270. <https://doi.org/10.1016/j.autcon.2016.08.001>.

619 Arashpour, M., R. Wakefield, N. Blismas, and T. Maqsood. 2015. “Autonomous production tracking

620 for augmenting output in off-site construction.” *Autom. Constr.*, 53: 13–21.
621 <https://doi.org/10.1016/j.autcon.2015.03.013>.

622 Assaf, M., M. Hussein, B. T. Alsulami, and T. Zayed. 2022. “A Mixed Review of Cash Flow Modeling:
623 Potential of Blockchain for Modular Construction.” *Buildings*.
624 <https://doi.org/10.3390/buildings12122054>.

625 Ayinla, K., F. Cheung, and M. Skitmore. 2022a. “Process Waste Analysis for Offsite Production
626 Methods for House Construction: A Case Study of Factory Wall Panel Production.” *J. Constr.*
627 *Eng. Manag.*, 148 (1). [https://doi.org/10.1061/\(ASCE\)CO.1943-7862.0002219](https://doi.org/10.1061/(ASCE)CO.1943-7862.0002219).

628 Ayinla, K., F. Cheung, and M. Skitmore. 2022b. “Process Waste Analysis for Offsite Production
629 Methods for House Construction: A Case Study of Factory Wall Panel Production.” *J. Constr.*
630 *Eng. Manag.*, 148 (1): 5021011. American Society of Civil Engineers.
631 [https://doi.org/10.1061/\(ASCE\)CO.1943-7862.0002219](https://doi.org/10.1061/(ASCE)CO.1943-7862.0002219).

632 BAMB. 2020. “MATERIALS PASSPORTS.” Accessed December 20, 2022.
633 <https://www.bamb2020.eu/topics/materials-passports/>.

634 Banks, C., R. Kotecha, J. Curtis, C. Dee, N. Pitt, and R. Papworth. 2018. “Enhancing high-rise
635 residential construction through design for manufacture and assembly - A UK case study.” *Proc.*
636 *Inst. Civ. Eng. Manag. Procure. Law*, 171 (4): 164–174. <https://doi.org/10.1680/jmapl.17.00027>.

637 Barkokebas, B., S. Khalife, M. Al-Hussein, and F. Hamzeh. 2021a. “A BIM-lean framework for
638 digitalisation of premanufacturing phases in offsite construction.” *Eng. Constr. Archit. Manag.*,
639 28 (8): 2155–2175. <https://doi.org/10.1108/ECAM-11-2020-0986>.

640 Barkokebas, B., C. Ritter, M. Al-Hussein, and X. Li. 2021b. “Simulation-based decision support for
641 production improvement using integrated ergonomic and productivity performance indicators.”
642 *Int. J. Simul. Process Model.*, 16 (2): 161–174. <https://doi.org/10.1504/IJSPM.2021.115867>.

643 Bataglin, F. S., D. D. Viana, C. T. Formoso, and I. R. Bulhões. 2017. “Application of BIM for
644 supporting decision-making related to logistics in prefabricated building systems.” *IGLC 2017 -*
645 *Proc. 25th Annu. Conf. Int. Gr. Lean Constr.*, 71–78.

646 Bataglin, F. S., D. D. Viana, C. T. Formoso, and I. R. Bulhões. 2020. “Model for planning and
647 controlling the delivery and assembly of engineer-to-order prefabricated building systems:

648 Exploring synergies between lean and BIM.” *Can. J. Civ. Eng.*, 47 (2): 165–177.
649 <https://doi.org/10.1139/cjce-2018-0462>.

650 Bhamu, J., and K. S. Sangwan. 2014. “Lean manufacturing: Literature review and research issues.” *Int.*
651 *J. Oper. Prod. Manag.*, 34 (7): 876–940. <https://doi.org/10.1108/IJOPM-08-2012-0315>.

652 Bortolini, R., C. T. Formoso, and D. D. Viana. 2019. “Site logistics planning and control for engineer-
653 to-order prefabricated building systems using BIM 4D modeling.” *Autom. Constr.*, 98 (February
654 2018): 248–264. Elsevier. <https://doi.org/10.1016/j.autcon.2018.11.031>.

655 Bovea, M. D., V. Pérez-Belis, V. Ibáñez-Forés, and P. Quemades-Beltrán. 2016. “Disassembly
656 properties and material characterisation of household small waste electric and electronic
657 equipment.” *Waste Manag.*, 53: 225–236. Elsevier.
658 <https://doi.org/https://doi.org/10.1016/j.wasman.2016.04.011>.

659 Breque, M., L. De Nul, and A. Petrides. 2021. *Industry 5.0 - Towards a sustainable, human- centric*
660 *and resilient European industry. Eur. Comm.*

661 Cao, J., E. Vakaj, R. K. Soman, and D. M. Hall. 2022. “Ontology-based manufacturability analysis
662 automation for industrialized construction.” *Autom. Constr.*, 139: 104277. Elsevier.

663 Chadegani, A., H. Salehi, M. M. Md Yunus, H. Farhadi, M. Fooladi, M. Farhadi, and N. Ale Ebrahim.
664 2013. “A comparison between two main academic literature collections: Web of science and
665 scopus databases.” *Asian Soc. Sci.*, 9 (5). <https://doi.org/10.5539/ass.v9n5p18>.

666 Chauhan, K., A. Peltokorpi, O. Seppänen, and K. Berghede. 2018. “Combining takt planning with
667 prefabrication for industrialized construction.” *IGLC 2018 - Proc. 26th Annu. Conf. Int. Gr. Lean*
668 *Constr. Evol. Lean Constr. Towar. Matur. Prod. Manag. Across Cult. Front.*, 848–857.

669 Chen, Y., Y. Zhou, W. Feng, Y. Fang, and A. Feng. 2022. “Factors That Influence the Quantification
670 of the Embodied Carbon Emission of Prefabricated Buildings: A Systematic Review, Meta-
671 Analysis and the Way Forward.” *Buildings*. <https://doi.org/10.3390/buildings12081265>.

672 Choi, J. O., B. K. Shrestha, Y. H. Kwak, and J. S. Shane. 2020. “Innovative Technologies and
673 Management Approaches for Facility Design Standardization and Modularization of Capital
674 Projects.” *J. Manag. Eng.*, 36 (5). [https://doi.org/10.1061/\(ASCE\)ME.1943-5479.0000805](https://doi.org/10.1061/(ASCE)ME.1943-5479.0000805).

675 Court, P. F., C. L. Pasquire, G. F. Gibb, and D. Bower. 2009. “Modular assembly with postponement

676 to improve health, safety, and productivity in construction.” *Pract. Period. Struct. Des. Constr.*,
677 14 (2): 81–89. [https://doi.org/10.1061/\(ASCE\)1084-0680\(2009\)14:2\(81\)](https://doi.org/10.1061/(ASCE)1084-0680(2009)14:2(81)).

678 Daniel, E. I., and O. Oshodi. 2022. “Lean-offsite-simulation nexus for housing construction: a state-of-
679 the-art review of the existing knowledge.” *Constr. Innov.* <https://doi.org/10.1108/CI-03-2022-0051>.

680

681 Darko, A., A. P. C. Chan, M. A. Adabre, D. J. Edwards, M. R. Hosseini, and E. E. Ameyaw. 2020.
682 “Artificial intelligence in the AEC industry: Scientometric analysis and visualization of research
683 activities.” *Autom. Constr.*, 112: 103081. Elsevier.
684 <https://doi.org/https://doi.org/10.1016/j.autcon.2020.103081>.

685 Darwish, M., O. Mohsen, Y. Mohamed, and M. Al-Hussein. 2020. “Integrated simulation and lean
686 approach for production line improvement in a prefabricated panelized homebuilding facility.”
687 *IGLC 28 - 28th Annu. Conf. Int. Gr. Lean Constr. 2020*, 649–660.

688 Demir, K. A., G. Döven, and B. Sezen. 2019. “Industry 5.0 and human-robot co-working.” *Procedia*
689 *Comput. Sci.*, 158: 688–695. Elsevier. <https://doi.org/https://doi.org/10.1016/j.procs.2019.09.104>.

690 Du, J., Y. Xue, V. Sugumaran, M. Hu, and P. Dong. 2022. “Improved biogeography-based optimization
691 algorithm for lean production scheduling of prefabricated components.” *Eng. Constr. Archit.*
692 *Manag.* <https://doi.org/10.1108/ECAM-04-2021-0311>.

693 Du, J., J. Zhang, D. Castro-lacouture, and Y. Hu. 2023. “Lean manufacturing applications in
694 prefabricated construction projects.” *Autom. Constr.*, 150 (February): 104790. Elsevier B.V.
695 <https://doi.org/10.1016/j.autcon.2023.104790>.

696 Van Eck, N. J., and L. Waltman. 2021. “Manual VOSviewer.” *Univeriteit Leiden*, (January): 54.

697 Ekanayake, E., G. Shen, and M. M. Kumaraswamy. 2020. “Critical capabilities of improving supply
698 chain resilience in industrialized construction in Hong Kong.” *Eng. Constr. Archit. Manag.*
699 Emerald Publishing Limited. <https://doi.org/https://doi.org/10.1108/ECAM-05-2020-0295>.

700 Feist, S., L. Sanhudo, V. Esteves, M. Pires, and A. A. Costa. 2022. “Semi-Supervised Clustering for
701 Architectural Modularisation.” *Buildings*, 12 (3). <https://doi.org/10.3390/buildings12030303>.

702 Gbadamosi, A.-Q., A.-M. Mahamadu, L. O. Oyedele, O. O. Akinade, P. Manu, L. Mahdjoubi, and C.
703 Aigbavboa. 2019. “Offsite construction: Developing a BIM-Based optimizer for assembly.” *J.*

704 *Clean. Prod.*, 215: 1180–1190. <https://doi.org/10.1016/j.jclepro.2019.01.113>.

705 Ghayeb, H. H., H. A. Razak, and N. H. Ramli Sulong. 2020. “Performance of dowel beam-to-column
706 connections for precast concrete systems under seismic loads: A review.” *Constr. Build. Mater.*
707 <https://doi.org/10.1016/j.conbuildmat.2019.117582>.

708 Ghobakhloo, M. 2018. “The future of manufacturing industry: a strategic roadmap toward Industry
709 4.0.” *J. Manuf. Technol. Manag.*, 29 (6): 910–936. <https://doi.org/10.1108/JMTM-02-2018-0057>.

710 Ghobakhloo, M. 2020. “Industry 4.0, digitization, and opportunities for sustainability.” *J. Clean. Prod.*,
711 252: 119869. Elsevier. <https://doi.org/https://doi.org/10.1016/j.jclepro.2019.119869>.

712 Gilchrist, A. 2016. *Industry 4.0: the industrial internet of things*. Springer.

713 Giriunas, K., H. Sezen, and R. B. Dupaix. 2012. “Evaluation, modeling, and analysis of shipping
714 container building structures.” *Eng. Struct.*, 43: 48–57.
715 <https://doi.org/10.1016/j.engstruct.2012.05.001>.

716 Goh, M., and Y. M. Goh. 2019. “Lean production theory-based simulation of modular construction
717 processes.” *Autom. Constr.*, 101: 227–244. <https://doi.org/10.1016/j.autcon.2018.12.017>.

718 Goodier, C., and A. Gibb. 2007. “Future opportunities for offsite in the UK.” *Constr. Manag. Econ.*
719 <https://doi.org/10.1080/01446190601071821>.

720 Gusmao Brissi, S., O. Wong Chong, L. Debs, and J. Zhang. 2022. “A review on the interactions of
721 robotic systems and lean principles in offsite construction.” *Eng. Constr. Archit. Manag.*, 29 (1):
722 383–406. <https://doi.org/10.1108/ECAM-10-2020-0809>.

723 Hammersley, M. 2001. “On ‘Systematic’ Reviews of Research Literatures: A ‘narrative’ response to
724 Evans & Benefield.” *Br. Educ. Res. J.*, 27 (5): 543–554. Routledge.
725 <https://doi.org/10.1080/01411920120095726>.

726 Hampson, I. 1999. “Lean production and the toyota production system or, the case of the forgotten
727 production concepts.” *Econ. Ind. Democr.*, 20 (3): 369–391. SAGE Publications Ltd 6 Bonhill
728 Street, London EC2A 4PU, UK. <https://doi.org/https://doi.org/10.1177/0143831X99203>.

729 Harden, A., and J. Thomas. 2015. “Mixed Methods and Systematic Reviews: Examples and Emerging
730 Issues.” *SAGE Handb. Mix. Methods Soc. Behav. Res.*

731 He, R., M. Li, V. J. L. Gan, and J. Ma. 2021. “BIM-enabled computerized design and digital fabrication

732 of industrialized buildings: A case study.” *J. Clean. Prod.*, 278.
733 <https://doi.org/10.1016/j.jclepro.2020.123505>.

734 Heravi, G., and M. Firoozi. 2017. “Production process improvement of buildings’ prefabricated steel
735 frames using value stream mapping.” *Int. J. Adv. Manuf. Technol.*, 89 (9–12): 3307–3321. The
736 International Journal of Advanced Manufacturing Technology. [https://doi.org/10.1007/s00170-](https://doi.org/10.1007/s00170-016-9306-9)
737 [016-9306-9](https://doi.org/10.1007/s00170-016-9306-9).

738 Heravi, G., M. F. M. F. M. F. M. F. Kebria, and M. Rostami. 2021. “Integrating the production and the
739 erection processes of pre-fabricated steel frames in building projects using phased lean
740 management.” *Eng. Constr. Archit. Manag.*, 28 (1): 174–195. [https://doi.org/10.1108/ECAM-03-](https://doi.org/10.1108/ECAM-03-2019-0133)
741 [2019-0133](https://doi.org/10.1108/ECAM-03-2019-0133).

742 Heravi, G., M. Rostami, and M. F. Kebria. 2020. “Energy consumption and carbon emissions
743 assessment of integrated production and erection of buildings’ pre-fabricated steel frames using
744 lean techniques.” *J. Clean. Prod.*, 253: 120045. Elsevier Ltd.
745 <https://doi.org/10.1016/j.jclepro.2020.120045>.

746 Hermann, M., T. Pentek, and B. Otto. 2016. “Design principles for industrie 4.0 scenarios.” *Proc. Annu.*
747 *Hawaii Int. Conf. Syst. Sci.*, 2016-March: 3928–3937. IEEE.
748 <https://doi.org/10.1109/HICSS.2016.488>.

749 Hopp, W. J., and M. L. Spearman. 2004. “To Pull or Not to Pull: What Is the Question?” *Manuf. Serv.*
750 *Oper. Manag.*, 6 (2). <https://doi.org/https://doi.org/10.1287/msom.1030.0028>.

751 Hosseini, M. R., I. Martek, E. K. Zavadskas, A. A. Aibinu, M. Arashpour, and N. Chileshe. 2018.
752 “Critical evaluation of off-site construction research: A Scientometric analysis.” *Autom. Constr.*,
753 87 (July 2017): 235–247. Elsevier. <https://doi.org/10.1016/j.autcon.2017.12.002>.

754 Hu, S., Y. Fang, and Y. Bai. 2021. “Automation and optimization in crane lift planning: A critical
755 review.” *Adv. Eng. Informatics*, 49: 101346. Elsevier.
756 <https://doi.org/https://doi.org/10.1016/j.aei.2021.101346>.

757 Hu, X., and H.-Y. Chong. 2021. “Environmental sustainability of off-site manufacturing: a literature
758 review.” *Eng. Constr. Archit. Manag.* <https://doi.org/10.1108/ECAM-06-2019-0288>.

759 Hussein, M., A. E. E. E. Eltoukhy, A. Karam, I. A. Shaban, and T. Zayed. 2021. “Modelling in off-site

760 construction supply chain management: A review and future directions for sustainable modular
761 integrated construction.” *J. Clean. Prod.*, 310 (August 2020): 127503. Elsevier Ltd.
762 <https://doi.org/10.1016/j.jclepro.2021.127503>.

763 Hussein, M., and T. Zayed. 2021. “Critical factors for successful implementation of just-in-time concept
764 in modular integrated construction: A systematic review and meta-analysis.” *J. Clean. Prod.*, 284:
765 124716. Elsevier Ltd. <https://doi.org/10.1016/j.jclepro.2020.124716>.

766 Innella, F., M. Arashpour, M. Asce, Y. Y. Bai, M. Asce, and Y. Y. Bai. 2019. “Lean Methodologies
767 and Techniques for Modular Construction: Chronological and Critical Review.” *J. Constr. Eng.
768 Manag.*, 145 (12): 04019076. [https://doi.org/10.1061/\(asce\)co.1943-7862.0001712](https://doi.org/10.1061/(asce)co.1943-7862.0001712).

769 Isaac, S., T. Bock, and Y. Stoliar. 2014. “A new approach to building design modularization.” *Procedia
770 Eng.*, 274–282.

771 Jansson, G., H. Johnsson, and D. Engström. 2014. “Platform use in systems building.” *Constr. Manag.
772 Econ.*, 32 (1–2): 70–82. <https://doi.org/10.1080/01446193.2013.793376>.

773 Jarkko, E., W. Lu, S. Lars, and O. Thomas. 2013. “Discrete event simulation enhanced value stream
774 mapping: An industrialized construction case study.” *Lean Constr. J.*, 2013: 47–65.

775 Jin, R., S. Gao, A. Cheshmehzangi, and E. Aboagye-Nimo. 2018. “A holistic review of off-site
776 construction literature published between 2008 and 2018.” *J. Clean. Prod.*, 202: 1202–1219.
777 Elsevier Ltd. <https://doi.org/10.1016/j.jclepro.2018.08.195>.

778 Kagermann, W. Wahlster, J. Helbig, H. Kagermann, W. Wahlster, and J. Helbig. 2013.
779 “Recommendations for implementing the strategic initiative INDUSTRIE 4.0.” *Final Rep. Ind.*, 4
780 (0): 82.

781 Kamble, S. S., A. Gunasekaran, and S. A. Gawankar. 2018. “Sustainable Industry 4.0 framework: A
782 systematic literature review identifying the current trends and future perspectives.” *Process Saf.
783 Environ. Prot.*, 117: 408–425. Elsevier.
784 <https://doi.org/10.1016/j.psep.2018.05.009>.

785 Kedir, F., and D. M. Hall. 2021. “Resource efficiency in industrialized housing construction – A
786 systematic review of current performance and future opportunities.” *J. Clean. Prod.*, 286. Elsevier
787 Ltd. <https://doi.org/10.1016/j.jclepro.2020.125443>.

788 Koh, L., G. Orzes, and F. J. Jia. 2019. "The fourth industrial revolution (Industry 4.0): technologies
789 disruption on operations and supply chain management." *Int. J. Oper. Prod. Manag.*, 39 (6): 817–
790 828. Emerald Publishing Limited. <https://doi.org/10.1108/IJOPM-08-2019-788>.

791 Kong, L., H. Li, H. Luo, L. Ding, and X. Zhang. 2018. "Sustainable performance of just-in-time (JIT)
792 management in time-dependent batch delivery scheduling of precast construction." *J. Clean.
793 Prod.*, 193: 684–701. <https://doi.org/10.1016/j.jclepro.2018.05.037>.

794 Kurdve, M. 2018. "Digital assembly instruction system design with green lean perspective-Case study
795 from building module industry." *Procedia CIRP*, 762–767.

796 Kurdve, M., J. Hildenbrand, and C. Jönsson. 2018. "Design for green lean building module production
797 - Case study." *Procedia Manuf.*, 594–601.

798 Laika, M., G. Heravi, M. Rostami, and S. Ahmadi. 2022. "Improving the Performance of Precast
799 Concrete Production Processes by Simultaneous Implementation of Lean Techniques and Root
800 Cause Analysis." *Iran. J. Sci. Technol. - Trans. Civ. Eng.*, 46 (0123456789): 2649–2666. Springer
801 International Publishing. <https://doi.org/10.1007/s40996-022-00839-4>.

802 Lasi, H., P. Fettke, H. G. Kemper, T. Feld, and M. Hoffmann. 2014. "Industry 4.0." *Bus. Inf. Syst. Eng.*,
803 6 (4): 239–242. <https://doi.org/10.1007/s12599-014-0334-4>.

804 Lean Construction Institute. 2022. "The Last Planner System® (LPS®)." Accessed October 21, 2022.
805 <https://leanconstruction.org/lean-topics/last-planner-system/>.

806 Lean Enterprise Institute. 2022. "Toyota Production System." Accessed March 13, 2022.
807 <https://www.lean.org/lexicon-terms/toyota-production-system/>.

808 Leminen, V., H. Eskelinen, S. Matthews, and J. Varis. 2013. "Development and utilization of a DFMA-
809 evaluation matrix for comparing the level of modularity and standardization in clamping systems."
810 *Mechanika*, 19 (6): 711–715. <https://doi.org/10.5755/j01.mech.19.6.5999>.

811 Lerche, J., P. Enevoldsen, and O. Seppänen. 2022. "Application of Takt and Kanban to Modular Wind
812 Turbine Construction." *J. Constr. Eng. Manag.*, 148 (2).
813 [https://doi.org/10.1061/\(ASCE\)CO.1943-7862.0002245](https://doi.org/10.1061/(ASCE)CO.1943-7862.0002245).

814 Li, L., Z. Li, X. Li, S. Zhang, and X. Luo. 2020. "A new framework of industrialized construction in
815 China: Towards on-site industrialization." *J. Clean. Prod.*, 244.

816 <https://doi.org/10.1016/j.jclepro.2019.118469>.

817 Li, L., H. Luan, X. Yin, Y. Dou, M. Yuan, and Z. Li. 2022. "Understanding Sustainability in Off-Site
818 Construction Management: State of the Art and Future Directions." *J. Constr. Eng. Manag.*
819 [https://doi.org/10.1061/\(ASCE\)CO.1943-7862.0002396](https://doi.org/10.1061/(ASCE)CO.1943-7862.0002396).

820 Li, Z., G. Q. Shen, and X. Xue. 2014. "Critical review of the research on the management of
821 prefabricated construction." *Habitat Int.*, 43: 240–249. Elsevier Ltd.
822 <https://doi.org/10.1016/j.habitatint.2014.04.001>.

823 Liker, J. 2020. *The Toyota Way (2nd Edition): 14 Management Principles From the World's Greatest*
824 *Manufacturer. McGraw-Hill*.

825 Lu, Y. 2017. "Journal of Industrial Information Integration Industry 4 . 0 : A survey on technologies ,
826 applications and open research issues." *J. Ind. Inf. Integr.*, 6: 1–10. Elsevier Inc.
827 <https://doi.org/10.1016/j.jii.2017.04.005>.

828 Lu, Y., X. Xu, and L. Wang. 2020. "Smart manufacturing process and system automation – A critical
829 review of the standards and envisioned scenarios." *J. Manuf. Syst.*

830 Luo, T., X. Xue, Y. Tan, Y. Wang, and Y. Zhang. 2021. "Exploring a body of knowledge for promoting
831 the sustainable transition to prefabricated construction." *Eng. Constr. Archit. Manag.*
832 <https://doi.org/10.1108/ECAM-03-2020-0154>.

833 Ma, Y., and E. Qiao. 2021. "Visualized Management System of Prefabricated Construction and
834 Installation Engineering Based on BIM and Machine Learning." *2021 IEEE Int. Conf. Ind. Appl.*
835 *Artif. Intell. IAAI 2021*, 138–143.

836 MacCarthy, B., P. G. Brabazon, and J. Bramham. 2003. "Fundamental modes of operation for mass
837 customization." *Int. J. Prod. Econ.*

838 Maddikunta, P. K. R., Q. V. Pham, P. B, N. Deepa, K. Dev, T. R. Gadekallu, R. Ruby, and M. Liyanage.
839 2022. "Industry 5.0: A survey on enabling technologies and potential applications." *J. Ind. Inf.*
840 *Integr.*, 26 (August 2021): 100257. Elsevier Inc. <https://doi.org/10.1016/j.jii.2021.100257>.

841 Malik, J. A., and S. Marathe. 2022. *Ecological and Health Effects of Building Materials*. Springer.

842 Martínez, S., A. Jardón, J. G. Vítores, and C. Balaguer. 2013. "Flexible field factory for construction
843 industry." *Assem. Autom.*, 33 (2): 175–183. <https://doi.org/10.1108/01445151311306708>.

844 Masood, R., J. B. P. Lim, V. A. González, K. Roy, and K. I. A. Khan. 2022. “A Systematic Review on
845 Supply Chain Management in Prefabricated House-Building Research.” *Buildings*.
846 <https://doi.org/10.3390/buildings12010040>.

847 Mignacca, B., and G. Locatelli. 2021. “Modular Circular Economy in Energy Infrastructure Projects:
848 Enabling Factors and Barriers.” *J. Manag. Eng.*, 37 (5). [https://doi.org/10.1061/\(ASCE\)ME.1943-](https://doi.org/10.1061/(ASCE)ME.1943-5479.0000949)
849 [5479.0000949](https://doi.org/10.1061/(ASCE)ME.1943-5479.0000949).

850 Mignacca, B., G. Locatelli, and A. Velenturf. 2020. “Modularisation as enabler of circular economy in
851 energy infrastructure.” *Energy Policy*, 139: 111371. Elsevier.
852 [https://doi.org/https://doi.org/10.1061/\(ASCE\)ME.1943-5479.0000949](https://doi.org/https://doi.org/10.1061/(ASCE)ME.1943-5479.0000949).

853 Mirshekarlou, B. R., C. Budayan, I. Dikmen, and M. T. Birgonul. 2021. “Development of a knowledge-
854 based tool for waste management of prefabricated steel structure projects.” *J. Clean. Prod.*, 323:
855 129140. Elsevier. <https://doi.org/https://doi.org/10.1016/j.jclepro.2021.129140>.

856 Mohandes, S. R., S. Abdelmageed, S. Hem, J. S. Yoo, T. Abhayajeewa, and T. Zayed. 2022.
857 “Occupational Health and Safety in Modular Integrated Construction projects: The case of crane
858 operations.” *J. Clean. Prod.*, 342: 130950. Elsevier.
859 <https://doi.org/https://doi.org/10.1016/j.jclepro.2022.130950>.

860 Mostafa, S., N. Chileshe, and T. Abdelhamid. 2016. “Lean and agile integration within offsite
861 construction using discrete event simulation A systematic literature review.” *Constr. Innov.*, 16
862 (4): 483–525. <https://doi.org/10.1108/CI-09-2014-0043>.

863 Mrugalska, B., and M. K. Wyrwicka. 2017. “Towards Lean Production in Industry 4 . 0.” *Procedia*
864 *Eng.*, 182: 466–473. The Author(s). <https://doi.org/10.1016/j.proeng.2017.03.135>.

865 Müller, J. 2020. “Enabling Technologies for Industry 5.0: Results of a workshop with Europe’s
866 technology leaders.” *Eur. Comm.*, (September): 19. Publications Office.
867 <https://doi.org/10.2777/082634>.

868 Nahavandi, S. 2019. “Industry 5.0—A human-centric solution.” *Sustainability*, 11 (16): 4371. MDPI.
869 <https://doi.org/https://doi.org/10.3390/su11164371>.

870 Nahmens, I., and L. H. L. H. Ikuma. 2012. “Effects of Lean Construction on Sustainability of Modular
871 Homebuilding.” *J. Archit. Eng.*, 18 (2): 155–163. [https://doi.org/10.1061/\(asce\)ae.1943-](https://doi.org/10.1061/(asce)ae.1943-)

872 5568.0000054.

873 National BIM Standard. 2022. “WHAT IS A BIM?” Accessed November 7, 2022.
874 <https://www.nationalbimstandard.org/faqs#faq1>.

875 Navaratnam, S., T. Ngo, T. Gunawardena, and D. Henderson. 2019. “Performance review of
876 prefabricated building systems and future research in Australia.” *Buildings*, 9 (2): 1–14.
877 <https://doi.org/10.3390/buildings9020038>.

878 Nguyen, K. T. Q., S. Navaratnam, P. Mendis, K. Zhang, J. Barnett, and H. Wang. 2020. “Fire safety of
879 composites in prefabricated buildings: From fibre reinforced polymer to textile reinforced
880 concrete.” *Compos. Part B Eng.* <https://doi.org/10.1016/j.compositesb.2020.107815>.

881 Nikakhtar, A., A. A. Hosseini, K. Y. Wong, and A. Zavichi. 2015. “Application of lean construction
882 principles to reduce construction process waste using computer simulation: A case study.” *Int. J.*
883 *Serv. Oper. Manag.*, 20 (4). <https://doi.org/10.1504/IJSOM.2015.068528>.

884 O’Connor, J. T., W. J. O’Brien, and J. O. Choi. 2015. “Standardization strategy for modular industrial
885 plants.” *J. Constr. Eng. Manag.*, 141 (9). [https://doi.org/10.1061/\(ASCE\)CO.1943-7862.0001001](https://doi.org/10.1061/(ASCE)CO.1943-7862.0001001).

886 Ohno, T., and N. Bodek. 1988. *Toyota production system: Beyond large-scale production*. New York:
887 Productivity Press.

888 Økland, A., A. Johansen, T. Beste, and E. Gjestebj. 2017. “Standardization and Modularization of
889 Prisons.” *Procedia Comput. Sci.*, 990–997.

890 Økland, A., A. Johansen, and N. O. E. Olsson. 2018. “Shortening lead-time from project initiation to
891 delivery: A study of quick school and prison capacity provision.” *Int. J. Manag. Proj. Bus.*, 11
892 (3): 625–649. <https://doi.org/10.1108/IJMPB-07-2017-0073>.

893 Oluleye, B. I., D. W. M. Chan, A. B. Saka, and T. O. Olawumi. 2022. “Circular economy research on
894 building construction and demolition waste: A global review of current trends and future research
895 directions.” *J. Clean. Prod.*, 131927. Elsevier.
896 <https://doi.org/https://doi.org/10.1016/j.jclepro.2022.131927>.

897 Ouldboukhitine, S.-E., R. Belarbi, I. Jaffal, and A. Trabelsi. 2011. “Assessment of green roof thermal
898 behavior: A coupled heat and mass transfer model.” *Build. Environ.*, 46 (12): 2624–2631. Elsevier.
899 <https://doi.org/https://doi.org/10.1016/j.buildenv.2011.06.021>.

900 Oztemel, E., and S. Gursev. 2020. "Literature review of Industry 4.0 and related technologies." *J. Intell.*
901 *Manuf.*, 31 (1): 127–182. Springer US. <https://doi.org/10.1007/s10845-018-1433-8>.

902 Pan, M., Y. Yang, Z. Zheng, and W. Pan. 2022. "Artificial Intelligence and Robotics for Prefabricated
903 and Modular Construction: A Systematic Literature Review." *J. Constr. Eng. Manag.*
904 [https://doi.org/10.1061/\(ASCE\)CO.1943-7862.0002324](https://doi.org/10.1061/(ASCE)CO.1943-7862.0002324).

905 Pasco, J., Z. Lei, and C. Aranas. 2022. "Additive Manufacturing in Off-Site Construction: Review and
906 Future Directions." *Buildings*, 12 (1). <https://doi.org/10.3390/buildings12010053>.

907 Peñaloza, G. A., D. D. Viana, F. S. Bataglin, C. T. Formoso, and I. R. Bulhões. 2016. "Guidelines for
908 integrated production control in engineer-to-order prefabricated concrete building systems:
909 Preliminary results." *IGLC 2016 - 24th Annu. Conf. Int. Gr. Lean Constr.*, 103–112.

910 Qi, B., M. Razkenari, A. Costin, C. Kibert, and M. Fu. 2021. "A systematic review of emerging
911 technologies in industrialized construction." *J. Build. Eng.*, 39 (December 2020): 102265. Elsevier
912 Ltd. <https://doi.org/10.1016/j.jobe.2021.102265>.

913 Qi, Q., and F. Tao. 2018. "Digital twin and big data towards smart manufacturing and industry 4.0: 360
914 degree comparison." *Ieee Access*, 6: 3585–3593. IEEE.
915 <https://doi.org/https://doi.org/10.1109/ACCESS.2018.2793265>.

916 Rada, M. 2018. "INDUSTRY 5.0 definition." Accessed September 20, 2022. [https://michael-
917 rada.medium.com/industry-5-0-definition-6a2f9922dc48](https://michael-rada.medium.com/industry-5-0-definition-6a2f9922dc48).

918 Ritter, C., R. D. Barkokebas, X. Li, and M. Al-Hussein. 2019. "Integrated ergonomic and productivity
919 analysis for process improvement of panelised floor manufacturing." *18th Int. Conf. Model. Appl.*
920 *Simulation, MAS 2019*, 174–180.

921 Rosarius, A., and B. García De Soto. 2021. "On-site factories to support lean principles and
922 industrialized construction." *Organ. Technol. Manag. Constr.*, 13 (1): 2353–2366.
923 <https://doi.org/10.2478/otmcj-2021-0004>.

924 El Sakka, F., K. Eid, T. Narciss, and F. Hamzeh. 2016. "Integrating lean into modular construction: A
925 detailed case study of company X." *IGLC 2016 - 24th Annu. Conf. Int. Gr. Lean Constr.*, 23–32.

926 Shafiq, S. I., C. Sanin, E. Szczerbicki, and C. Toro. 2016. "Virtual engineering factory: Creating
927 experience base for industry 4.0." *Cybern. Syst.*, 47 (1–2): 32–47. Taylor & Francis.

928 Shafiq, S. I., C. Sanin, C. Toro, and E. Szczerbicki. 2015. "Virtual engineering object (VEO): Toward
929 experience-based design and manufacturing for industry 4.0." *Cybern. Syst.*, 46 (1–2): 35–50.
930 Taylor & Francis. <https://doi.org/https://doi.org/10.1080/01969722.2015.1007734>.

931 Snatkin, A., K. Karjust, J. Majak, T. Aruväli, and T. Eiskop. 2013. "Real time production monitoring
932 system in SME." *Est. J. Eng.*, 19 (1). <https://doi.org/https://doi.org/10.3176/eng.2013.1.06>.

933 Su, M., B. Yang, and X. Wang. 2022. "Research on Integrated Design of Modular Steel Structure
934 Container Buildings Based on BIM." *Adv. Civ. Eng.*, 2022. <https://doi.org/10.1155/2022/4574676>.

935 Thai, H.-T., T. Ngo, and B. Uy. 2020. "A review on modular construction for high-rise buildings."
936 *Structures*. <https://doi.org/10.1016/j.istruc.2020.09.070>.

937 Thajudeen, S., M. Lennartsson, F. Elgh, and P. J. Persson. 2020. "Parametric modelling of steel
938 connectors in a glulam based post and beam building system - Towards a flexible product platform
939 approach." *Adv. Transdiscipl. Eng.*, 564–573.

940 Vakaj, E., F. Cheung, J. Cao, A.-R. H. Tawil, and P. Patlakas. 2023. "An ontology-based cost estimation
941 for offsite construction." *J. Inf. Technol. Constr.*, 28: 220–245. International Council for Research
942 and Innovation in Building and Construction.

943 Van Der Veer, H., and A. Wiles. 2008. "Achieving Technical Interoperability: the ETSI Approach."
944 *Eur. Telecommun. Stand. Inst.*, (3): 29.

945 Viana, D. D., I. D. Tommelein, and C. T. Formoso. 2017. "Using modularity to reduce complexity of
946 industrialized building systems for mass customization." *Energies*, 10 (10).
947 <https://doi.org/10.3390/en10101622>.

948 Vithanage, S. C., M. Sing, P. Davis, and M. Pillay. 2022. "Systematic review on the identification of
949 safety risks in off-site manufacturing (OSM)." *J. Eng. Des. Technol.*
950 <https://doi.org/10.1108/JEDT-12-2020-0498>.

951 Vogel-Heuser, B., and D. Hess. 2016. "Guest Editorial Industry 4.0-Prerequisites and Visions." *IEEE*
952 *Trans. Autom. Sci. Eng.*, 13 (2): 411–413. <https://doi.org/10.1109/TASE.2016.2523639>.

953 Wang, M., M. S. Altaf, M. Al-Hussein, and Y. Ma. 2020a. "Framework for an IoT-based shop floor
954 material management system for panelized homebuilding." *Int. J. Constr. Manag.*, 20 (2): 130–
955 145. <https://doi.org/10.1080/15623599.2018.1484554>.

956 Wang, M., C. C. Wang, S. Sepasgozar, and S. Zlatanova. 2020b. “A systematic review of digital
957 technology adoption in off-site construction: Current status and future direction towards industry
958 4.0.” *Buildings*. <https://doi.org/10.3390/buildings10110204>.

959 Wang, X., Q. Du, C. Lu, and J. Li. 2022. “Exploration in carbon emission reduction effect of low-
960 carbon practices in prefabricated building supply chain.” *J. Clean. Prod.*, 368: 133153. Elsevier.
961 <https://doi.org/https://doi.org/10.1016/j.jclepro.2022.133153>.

962 Wang, Z., H. Hu, J. Gong, X. Ma, and W. Xiong. 2019. “Precast supply chain management in off-site
963 construction: A critical literature review.” *J. Clean. Prod.*
964 <https://doi.org/10.1016/j.jclepro.2019.05.229>.

965 Wesz, J. G. B., C. T. Formoso, and P. Tzortzopoulos. 2018. “Planning and controlling design in
966 engineered-to-order prefabricated building systems.” *Eng. Constr. Archit. Manag.*, 25 (2): 134–
967 152. <https://doi.org/10.1108/ECAM-02-2016-0045>.

968 Wulfsberg, J. P. 2017. “Industry 4.0 and Lean Management–Synergy or Contradiction?”
969 https://doi.org/https://doi.org/10.1007/978-3-319-66926-7_39.

970 Xu, G., M. Li, C. H. C.-H. C. H. Chen, and Y. Wei. 2018. “Cloud asset-enabled integrated IoT platform
971 for lean prefabricated construction.” *Autom. Constr.*, 93 (September 2017): 123–134. Elsevier.
972 <https://doi.org/10.1016/j.autcon.2018.05.012>.

973 Xu, X., Y. Lu, B. Vogel-Heuser, and L. Wang. 2021. “Industry 4.0 and Industry 5.0—Inception,
974 conception and perception.” *J. Manuf. Syst.*, 61 (September): 530–535. Elsevier Ltd.
975 <https://doi.org/10.1016/j.jmsy.2021.10.006>.

976 Yazdi, A. J., A. A. F. Fini, and P. Forsythe. 2020. “An Integrated Product Planning and Design Platform
977 in the Context of Housebuilding Industry.” *Constr. Res. Congr. 2020 Comput. Appl. - Sel. Pap.*
978 *from Constr. Res. Congr. 2020*, 802–811.

979 Ye, Z., K. Giriunas, H. Sezen, G. Wu, and D.-C. Feng. 2021. “State-of-the-art review and investigation
980 of structural stability in multi-story modular buildings.” *J. Build. Eng.*
981 <https://doi.org/10.1016/j.jobbe.2020.101844>.

982 Yin, X., H. Liu, Y. Chen, and M. Al-Hussein. 2019. “Building information modelling for off-site
983 construction: Review and future directions.” *Autom. Constr.*, 101 (October 2018): 72–91. Elsevier.

984 <https://doi.org/10.1016/j.autcon.2019.01.010>.

985 Yu, H., M. Al-Hussein, S. Al-Jibouri, and A. Telyas. 2013. "Lean Transformation in a Modular
986 Building Company: A Case for Implementation." *J. Manag. Eng.*, 29 (1): 103–111.
987 [https://doi.org/10.1061/\(asce\)me.1943-5479.0000115](https://doi.org/10.1061/(asce)me.1943-5479.0000115).

988 Zabihi, H., F. Habib, and L. Mirsaedie. 2013. "Definitions, concepts and new directions in
989 Industrialized Building Systems (IBS)." *KSCE J. Civ. Eng.*, 17 (6).
990 <https://doi.org/10.1007/s12205-013-0020-y>.

991 Zairul, M. 2021. "The recent trends on prefabricated buildings with circular economy (CE) approach."
992 *Clean. Eng. Technol.* <https://doi.org/10.1016/j.clet.2021.100239>.

993 Zhang, H., and L. Yu. 2020. "Dynamic transportation planning for prefabricated component supply
994 chain." *Eng. Constr. Archit. Manag.*, 27 (9): 2553–2576. <https://doi.org/10.1108/ECAM-12-2019-0674>.

995 0674.

996 Zhang, Y., Z. Lei, S. Han, A. Bouferguene, and M. Al-Hussein. 2020. "Process-Oriented Framework
997 to Improve Modular and Offsite Construction Manufacturing Performance." *J. Constr. Eng.
998 Manag.*, 146 (9). [https://doi.org/10.1061/\(asce\)co.1943-7862.0001909](https://doi.org/10.1061/(asce)co.1943-7862.0001909).

999 Zhong, R. Y., X. Xu, E. Klotz, and S. T. Newman. 2017. "Intelligent Manufacturing in the Context of
1000 Industry 4.0: A Review." *Engineering*, 3 (5). <https://doi.org/10.1016/J.ENG.2017.05.015>.

1001

1002

1003

1004

1005

1006

1007

1008

1009

1010

1011

1012 **Tables**

1013 **Table 1.** Summary of I4.0 & I5.0 design principles

Design Principle	Definition
Industry 4.0	
Interoperability	the capability of different production equipment, intelligent products, control systems, and stakeholders to interconnect and interact in a value network to enhance information sharing and exchange (Lu 2017).
Virtualisation	the creation of digital twins of physical systems to predict and optimise manufacturing performance (Qi and Tao 2018).
Decentralisation	the quality of smart elements and stakeholders in a value network to autonomously analysis data and take decisions in pursuit of shared organisational objectives (Gilchrist 2016).
Real-time efficiency	the quality of collecting, communicating, analysing, monitoring, and sharing data in real-time to facilitate timely decisions (Hermann et al. 2016).
Service orientation	the strategic focus of production systems on customers’ needs and expectations, encouraging timely responses to the market (Kamble et al. 2018).
Modularity	the capability of the production system to flexibly adapt to ever-changing market conditions by adopting more agile supply chain mindset (Ghobakhloo 2018).
Industry 5.0	
Human centricity	the prioritisation of workers’ needs and interests in a production system, over technology requirements (Nahavandi 2019).
Environmental Sust.	the pursuit of greener production systems respecting the planetary boundaries by promoting a circular economy mindset (Rada 2018).
Resilience	the capability of the production system to withstand potential supply chain disruptions, especially during the times of emergencies and crises (Breque et al. 2021).

1014

1015 **Table 2.** Keywords and interchangeable/related terms used in the search.

Keyword	Synonymous/ Related Terms
Off-site construction	“Off-site construction” OR “Off site construction” OR “Offsite construction” OR “Offsite manufacturing” OR “Offsite manufacture” OR “Off-site manufacturing” OR “Off-site manufacture” OR “Off site manufacturing” OR “Off site manufacture” OR “Prefabricated construction” OR “Pre-fabricated construction” OR “Prefabricated building” OR “Pre-fabricated building” OR “Precast Construction” OR “Pre-cast Construction” OR “Industrialized building” OR “industrialised construction” OR “Industrialized construction” OR “modular construction” OR “modular building”
Lean	AND lean OR “value stream mapping” OR just-in-time OR “just in time” OR kaizen OR “process improvement” OR pull-system OR “pull system” OR Kanban OR 5S OR 5why OR “continuous flow” OR “Visual Management” OR standardisation OR standardization OR “takt time” OR “Single-Minute Exchange of Die” OR “Single Minute Exchange of Die” OR “Total Productive Maintenance” OR “Production Leveling” OR “Production Levelling” OR Heijunka OR Poka-Yoke OR Jidoka OR Autonomation

1016 **Table 3.** Addressed resilience components/traits in lean-OSC literature.

Resilience components	Resilience traits	lean-OSC tools/concepts	lean-OSC Literature
Resourcefulness	personal security	Health & safety tools	(Ritter et al. 2019)
Resourcefulness	collaborative information exchange & decision making	BIM	(Bataglin et al. 2020)
Resourcefulness	collaborative forecasting	BIM	(Xu et al. 2018)
Flexibility	production postponement	JIT	(Zhang and Yu 2020)
Flexibility	modular product design	Design modularisation	(Feist et al. 2022)
Flexibility	multiple uses	standardisation	(Antoniou and Marinelli, 2020)
Adaptability	lead time reduction	Process simulation	(Zhang et al. 2020)
Efficiency	failure prevention	TPM	(Heravi et al. 2021)
Efficiency	rework avoidance	Process simulation	(El Sakka et al., 2016)
Efficiency	labour productivity	Process simulation	(Afifi et al. 2020)
Efficiency	waste elimination	Process simulation	(Ayinla et al., 2022)
Efficiency	learning from experience	standardisation	(Antoniou and Marinelli 2020)
Visibility	efficient IT system & information exchange	BIM	(Bortolini et al. 2019)
Visibility	products, assets, people visibility	LCA, health & safety tools, process simulation	(Kurdve et al. 2018)
Anticipation	deploying tracking and tracing tools	module tracking technology, takt planning	(Wang et al. 2020a)
Anticipation	monitoring early warning signals	Process simulation	(Afifi et al. 2020)
Anticipation	cross training	cross-training	(Goh and Goh 2019)
Dispersion	distributed decision making	LPS, optimisation models, mass-customisation platforms	(Isaac et al. 2014), (Wesz et al. 2018), (Yazdi et al. 2020)

1017

1018 **Figure Captions**

1019 **Fig. 1.** The number publications on lean-OSC literature since 2007

1020 **Fig. 2.** Research design

1021 **Fig. 3.** Major lean-OSC research network

1022 **Fig. 4.** Minor lean-OSC research networks

1023 **Fig. 5.** lean-OSC literature themes in the lens of I4.0 & I5.0 design principle versus supporting
1024 tools/concepts (Note: digits between parentheses represent the number of connections revealed
1025 from literature)